

Twin City Water Clinic Laboratory Test Report

Minnesota State Laboratory ID# 027-053-119
 Wisconsin State Laboratory ID# 105-10117
 Wisconsin DNR Lab ID #399073400

Client: Adrian School

Address: Advanced Health safety & Security
 105 Third Street
 Balaton, MN 56115

Report Number: 18-01911
Sample Receipt Date: 2/6/18
Sample Prep. Date: 2/6/18
Sample Prep. Time: 12:00
Report Issue Date: 03/13/18

Twin City Water Clinic Inc.
617 13th Avenue South
Hopkins, MN 55343
Phone: (952)935-3556
Fax: (952)935-5077

X No samples were subcontracted; or the above test result(s) with '**' designation were produced by a subcontracted laboratory. [Laboratory name; address; MDH Lab ID#]. The subcontracted laboratory maintains MDH Certification for the field(s) of testing performed.

Laboratory Sample ID	Analyte	Sample Location	Parameter	Sample Collection		Sample Analysis		Test	
				Date	Time	Date	Time	Results	Units
18-01911	Lead	Middle Sch. Hall 100 Corridor	Drinking Water	01/31/18	13:35	02/09/18	12:15	<2.0	µg/L
18-01912	Lead	Gym entrance WF	Drinking Water	01/31/18	13:26	02/09/18	12:21	<2.0	µg/L
18-01913	Lead	Wellness Center WF	Drinking Water	01/31/18	13:38	02/09/18	12:26	<2.0	µg/L
18-01914	Lead	400 Corridor WF	Drinking Water	01/31/18	13:39	02/09/18	12:31	2.76	µg/L
18-01915	Lead	Lunch RM	Drinking Water	01/31/18	13:41	02/09/18	12:36	3.25	µg/L
18-01916	Lead	Kitchen Sink	Drinking Water	01/31/18	13:44	02/13/18	12:47	289.52	µg/L
18-01917	Lead	Middle School Gym	Drinking Water	01/31/18	13:48	02/12/18	11:15	<2.0	µg/L
18-01918	Lead	300 Corridor	Drinking Water	01/31/18	13:50	02/12/18	11:20	5.15	µg/L
18-01919	Lead	600 Corridor Boys Locker RM	Drinking Water	01/31/18	13:51	02/12/18	11:25	<2.0	µg/L
18-01920	Lead	700 Corridor	Drinking Water	01/31/18	13:53	02/12/18	11:35	<2.0	µg/L
18-01921	Lead	Home EC Instructor	Drinking Water	01/31/18	14:01	02/12/18	11:40	<2.0	µg/L
18-01922	Lead	Home EC #2	Drinking Water	01/31/18	14:03	02/12/18	11:45	3.52	µg/L
18-01923	Lead	(M) Cafeteria Middle School	Drinking Water	01/31/18	14:35	02/12/18	11:50	<2.0	µg/L
18-01924	Lead	(M) Middle School Gym Hall	Drinking Water	01/31/18	14:39	02/13/18	12:55	<2.0	µg/L
18-01925	Lead	(M) Kitchen Island	Drinking Water	01/31/18	14:43	02/13/18	13:00	<2.0	µg/L
18-01926	Lead	(M) Kitchen N side sink	Drinking Water	01/31/18	14:46	02/13/18	13:04	4.75	µg/L
18-01927	Lead	(M) Upstairs Commons	Drinking Water	01/31/18	14:48	02/13/18	13:08	<2.0	µg/L
18-01928	Lead	(M) Upstairs RM 216 Hall	Drinking Water	01/31/18	14:52	02/13/18	13:13	<2.0	µg/L

Approved methods used in analyzing the samples listed above have the following reporting levels:
 SM3113 - Lead, 2.0 µg / L
 Maximum contaminant level: Lead, 15.0 µg / L

Sample Collected by: X Client TCWC

Sample Temp.: 14 °C

Notes:

Discussion:

Approved By:


 Bill Van Arsdale
 Laboratory Manager

The results listed in this report apply only to the above listed samples. All routine quality assurance procedures were followed, unless otherwise noted. This analytical report must be reported in its entirety. All methods are certified by the Minnesota Department of Health, unless otherwise noted.

Twin City Water Clinic
 617 13th Ave South
 Hopkins, MN 55343
 (952) 935-3556 FAX (952) 935-5077

CHAIN-OF-CUSTODY RECORD

Client: Advanced Health Safety & Security Client Address: 105 Third Street Balaton, MN 56115 Customer Phone No: Brian Parrie 605-430-8842	Contract Lab Information Ship To: Ship Date: Courier:
--	--

Lab ID # Lab use only	Date	Time	Sample ID	Sample Location	Lead	Sample by
	1/31/18	1:25	001	Middle School Hall 100 Corridor	X	SP
	1/31/18	1:26	002	Gym Entrance WF	X	SP
	1/31/18	1:38	003	Wellness Center WF	X	SP
	1/31/18	1:39	004	400 Corridor WF	X	SP
	1/31/18	1:41	005	Lunch Rm	X	SP
	1/31/18	1:44	006	Kitchen Hot Sink	X	SP
	1/31/18	1:46	007	Middle School Gym	X	SP
	1/31/18	1:50	008	300 Corridor	X	SP
	1/31/18	1:51	009	600 Corridor Boys Locker Rm	X	SP
	1/31/18	1:53	010	700 Corridor	X	SP
	1/31/18	2:01	011	Home EC class room ^{Instruction}	X	SP
	1/31/18	2:03	012	Home EC unit #2	X	SP
	1/31/18	2:35	013	(M) Cafeteria Middle School	X	SP
	1/31/18	2:35	014	(M) Middle School Gym Hall	X	SP
	1/31/18	2:43	015	(M) Kitchen Island	X	SP
	1/31/18	2:46	016	(M) Kitchen Northside Sink	X	SP
	1/31/18	2:48	017	(M) upstairs Commons	X	SP
	1/31/18	2:52	018	(M) upstairs km 216 Hall	X	SP

Relinquished By:	Date	Time	Relinquish To:	Date	Time

Container Intact	Yes	No	Correct Container	Yes	No		Comments:
Cooled	Yes	No	Temperature Blank	Yes	No	(°C)	

Field of testing: Lead SM3113B